Job Name/Location: Tag No:

For: File Resubmit Date: Approval Other PO No.:

GC: **Architect:** Mech: Engr:

Rep:

(Project Manager)

# LMU601HV Multi F MAX Outdoor Unit 5.0 Ton Heat Pump





### Performance:

Cooling Capacity (MinRated-Max., Btu/h)	10,800~60,000~65,000
Heating Capacity (MinRated-Max., Btu/h)	12,420~64,000~68,000
Max. Heating Capacity at 17°F (Btu/h)	57,590
Max. Heating Capacity at 5°F (Btu/h)	52,840
Max. Heating Capacity at -4°F (Btu/h)	46,220
Cooling COP @95°F (Rated)	3.31
Heating COP @47°F (Rated)	3.45

Cooling Nominal Test Conditions: Indoor: 80°F DB / 67°F WB Outdoor: 95°F DB / 75°F WB

Heating Nominal Test Conditions: Indoor: 70°F DB / 60°F WB Outdoor: 47°F DB / 43°F WB

#### **Electrical:**

Power Supply (V/Hz/Ø) <sup>1</sup>	208-230V, 60, 1
MOP (A)	40
MCA (A)	32.7
Cooling Rated Amps (A)	30.4
Heating Rated Amps (A)	30.4
Compressor (A)	22.0
Fan Motor (A)	1.6 x 2
Locked Rotor Amps (A)	22
I	

MOP - Maximum Overcurrent Protection

MCA - Minimum Circuit Ampacity

#### Piping:

Refrigerant Charge (lbs.)	11.46
Liquid Line Connection (in., O.D.)	Ø3/8 x 1
Vapor Line Connection (in., O.D.)	Ø3/4 x 1
Maximum Total Piping <sup>2</sup> (ft.)	475.7
Min. / Max. ODU to IDU Piping <sup>3</sup> (ft.)	32.8 / 229.6
Piping Length⁴ (no add'l refrigerant, ft.)	180.4
Maximum Elevation between ODU and IDU (ft.)	98.4
Maximum Elevation between IDU and IDU (ft.)	49.2

ODU = Outdoor Unit

IDU = Indoor Unit

#### **Features:**

- R1 Scroll (Variable Speed) Compressor
- · Defrost / Deicing Low ambient cooling
- · Restart delay (three [3] minutes)

- Auto operation
- down to 14°F
- Auto restart Soft start
- · Self diagnosis

## **Optional Accessories:**

- ☐ PI-485 PMNFP14A1 ☐ AC Smart 5 - PACS5A000 ☐ ACP 5 - PACP5A000
- ☐ MultiSITE™ Comm. Mgr. PBACNBTR0A
- ☐ Power Distribution Indicator (PDI)

Premium - PQNUD1S41

- ☐ Mobile LGMV PLGMVW100
- ☐ Low Ambient Wind Baffle (Cooling
- Operation Down to -4°F) ZLABGP04A x2
- ☐ Drain Pan Heater PQSH1200

## Required<sup>5</sup> Accessories:

- ☐ 2 Port BD Unit PMBD3620 ☐ 3 Port BD Unit - PMBD3630
- ☐ 4 Port BD Unit PMBD3640
- ☐ 4 Port BD Unit PMBD3641

#### **Operating Range:**

Cooling	°F DB) <sup>15</sup>		14	to 118
Heating	(°F WB)		-4	to +64

#### **Unit Data:**

Refrigerant Type	R410A
Refrigerant Control	EEV
Sound Pressure (Cool / Heat) ±1 dB(A) <sup>6</sup>	56 / 58
Net / Shipping Weight (lbs.)	218 / 243
Heat Exchanger Coating	Gold Fin™
Minimum No. of Indoor Units	2
Maximum No. of Indoor Units	8

#### Compressor:

Туре	R1 Scroll
Quantity	1
Oil / Type	FVC68D

#### Fan:

I WIII	
Туре	Propeller
Quantity	2
Motor / Drive	Brushless Digitally Controlled/Direct
Max. Airflow Rate (CFM)	2,119 x 2

#### Notes:

- 1. Acceptable operating voltage: 187V 253V
- 2. Piping lengths are equivalent.
- 3. 180.4 ft. of Main Piping + 49.2 ft. of Branch Piping.
- 4. 49.2 ft. of Main Piping + 131.2 of Branch Piping.
- 5. At least one branch distribution (BD) unit is required for system operation; a maximum of two can be installed per ODU with the use of a Y-branch accessory (PMBL5620).
- 6. Sound pressure levels are tested in an anechoic chamber under ISO Standard 3745.
- 7. All power / communication cable to be minimum 14 AWG from the ODU to the BD unit, and 14 AWG from the BD unit to the IDU.


  8. All power / communication cable to be 4-conductor, stranded, shielded or un-
- shielded, and must comply with applicable local and national codes. If shielded, the wire must be grounded to the chassis at the ODU only.
- 9. Power wiring size must comply with the applicable local and national codes.
- 10. See the Engineering Manual Capacity Tables for ODU sensible and latent capacities.
- 11. See the Engineering Manual Combination Tables for allocation of ODU rated capacity to each connected IDU when all are calling for full capacity. Allocation percentages should be applied to ODU capacity at design conditions.
- 12. This data is rated 0 ft. above sea level, with 147.6 ft. of refrigerant pipe length, and 0 ft. level difference between ODU and IDUs. All capacities are net with a combination ratio between 95 - 105%.
- 13. Must follow installation instructions in the applicable LG installation manual.
- 14. See the Engineering Manual Capacity Tables for ODU capacity at design conditions.
- 15. Installation of an optional Low Ambient Wind Baffle Kit will allow operation down to -4°F in cooling mode










# LMU601HV Multi F MAX Outdoor Unit 5.0 Ton Heat Pump





# LMU601HV Multi F MAX Outdoor Unit 5.0 Ton Heat Pump





Example: outdoor unit with eight (8) indoor units and two (2) branch distri-

bution units connected. ODU: Outdoor Unit. IDU: Indoor Unit.

BDU: Branch Distribution Unit(s).


A: Main Pipe.

B: Branch Pipe (Branch Distribution Unit[s] to Indoor Unit[s]).

### Multi F MAX Outdoor Unit Refrigerant Piping System Limitations.

	Total piping length (ΣA + ΣB)	≤475.7 feet	
Pipe Length	I Main pipe (Outdoor Unit to Branch Distribution Units: A) I	Minimum for Each (A) Piping Segment	16.4 feet
		Maximum (ΣA)	≤180.4 feet
(ELF = Equivalent Length of pipe in Feet)	Total branch piping length (ΣΒ)	≤295.3 feet	
Length of pipe in recty	Branch pipe (Branch Distribution Units to Indoor Units: B)	Minimum	16.4 feet
	Branch pipe (Branch Distribution Onlts to Indoor Onlts: B)	Maximum	≤49.2 feet
Elevation Differential If outdoor unit is above or below indoor unit (h1)			≤98.4 feet
(All Elevation	Between the farthest two indoor units (h2)	≤49.2 feet	
Limitations are	Between branch distribution unit and farthest connected in	≤32.8 feet	
Measured in Actual Feet)  Between branch distribution units (h4)		≤49.2 feet	

#### Installing the Unit



### Multi F MAX Piping Sizes.

Piping	Main Pipe A (inch)	Branch Pipe B
Liquid	Ø3/8	Depends on the size of
Vapor	Ø3/4	the indoor unit piping.